## ENGINEERING DEPARTMENT.

### BANGALORE BUILDINGS DIVISION, BANGALORE.

*Notification dated 24th April* 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, Bangalore, up to 27th May 1933, (2 P.M.,) on for constructing a buildiug for locating the Maharatta and Urdu Primary Girls' School for Mysore State Troops at Hebbal, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1933:—

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore Buildings Division, Bangalore, between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and in figures.

4. Each tender must be accompanied by a deposit of rupees three hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a building for locating the Maharatta and Urdu Primary Girls' School for Mysore State Troops, Bangalore, in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Bangalore Buildings Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate rates will not be accepted.

10. No claims of enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements, quality of work, etc., the dicision of the Chief Engineer will be final and legally binding over the contractors.

Abstract of estimate for constructing a building for locating the Maharatta and Urdu Primary Girls' School for Mysore State Troops at Hebbal, Bangalore.

| Sl. No. | Items of work | Unit | Quantity | Rate in figures | Rate in words |
|---|---|---|---|---|---|
| | | | | Rs. a. p. | Rs. a. p. |
| 1 | Earthwork excavation for foundation ... | C.yd. | 109 | | |
| 2 | Filling in basement with excavated earth and consolidation. | " | 75 | | |
| 3 | Concrete in Mortar .. ... | C.ft. | 845 | | |
| 4 | Burnt stone in clay ... ... | " | 2,778 | | |
| 5 | Burnt brick in clay .. ... | " | 4,501 | | |
| 6 | Burt brick in mortar ... ... | " | 179 | | |
| 7 | Arch work, brunt brick in mortar ... | " | 41 | | |
| 8 | Burnt stone slabs 5" to 6" thick dressed and fixed. | S.ft. | 390 | | |
| 8a | Burnt stone slabs 4" dressed and fixed .. | " | 173 | | |
| 9 | Teak wood doors, with battened shutters and Iron work complete. | " | 98 | | |
| 10 | Teak wood windows, with four panneled shutters, and teak wood perforated ventilator on top, with Iron bars complete. | " | 312 | | |

| Sl. No. | Item of work | Unit | Quantity | Rate in figures | Rate in words |
|---|---|---|---|---|---|
| | | | | Rs. a. p. | Rs. a. p. |
| 11 | Teak wood glazed semi-circular ventilators. . | S.ft. | 25 | | |
| 12 | Teak wood wrought and put up with wood oiling. | C.ft. | 172·63 | | |
| 13 | Roofing with first class Mangalore tiles on teak reepers with nails complete | Sqr. | 27·82 | | |
| 14 | Mangalore Ridge Tiles set in cement mortar. | R.ft. | 107 | | |
| 15 | Plastering with mortar inside ... | Sqr. | 80·42 | | |
| 16 | Rough plastering outside marking with trowel with cement wash as shown in plan. | ,, | 18·15 | | |
| 17 | Chunam patties on rough plaster outside with white washing complete as per plan. | R.ft. | 803 | | |
| 18 | White washing two coats ... ... | Sqr. | 80·42 | | |
| 19 | Pointing the basement with cement mortar. | ,, | 7·94 | | |
| 20 | Chacolate painting two coats ... | ,, | 5·45 | | |
| 21 | Flooring with cuddapah slabs on 3" thick concrete bed with cement pointing. | ,, | 13·57 | | |
| 22 | Chunam borders over roof 6" thick ... | R.ft. | 89 | | |
| 23 | Teak wood cave board with painting ... | ,, | 318 | | |
| 24 | Teak wood finials ... ... | Each | 4 | | |
| 25 | Teak wood pendents ... ... | ,, | 8 | | |
| 26 | Providing teak wood gate topass ages of central rooms with iron works, painting complete. | S.ft. | 48 | | |
| 27 | Providing teak wood gate to main entrance with sinc sheet covering iron works, painting complete. | ,, | 66 | | |
| 28 | Drilling holes in gate pillars ... | Each | 8 | | |
| 29 | Cutting niches in bearing slabs to hold struts in front. | ,, | 10 | | |
| 30 | Clearing site and levelling ground ... | Lump sum rupees | | | |

A. TANDONI RAO,
*Executive Engineer,*

## SRI CHAMARAJENDRA WATER WORKS DIVISION.

*Abstract Notification.*

The attention of the public is invited to the notification, calling for tenders for conveying alum, pipes and other heavy materials from Bangalore City Station to Thippagondanahalli, published in Part VI, page 520 of the *Mysore Gazette*, dated 4th May 1933.

The last date fixed for receiving tenders is 22nd May 1933.

---

*Notice of sale of scrap iron.*

Sealed tenders are invited up 2 P.M. on 28th May 1933 for the purchase of iron scrap consisting of unserviceable mortar mills, corrugated iron buckets, mild steel bars, mortar pans, hammers, mamties, pickaxes, etc., released from works.

2. The rate per ton at which the material can be purchased at site of works or stores should be clearly noted and no claim for dismantling, conveying or other incidental expenses can be allowed.

3. The material can be inspected on any working date obtaining the permission of the undersigned.

4. The tenders should be enclosed in sealed cover and delivered at the office on or before the time stipulated above.

5. Each tender must be accompanied by an earnest deposit of Rs. 50. The deposit of unsuccessful tenderers will be returned immediately after one of the tenders is accepted.